

PLUMBING FIXTURE SCHEDULE						
Unless otherwise noted fixtures are based on American Standard, equals by Kohler or Crane may be submitted for approval. Drainage items are based on Zurn, equals by Josam or J.R. Smith may be submitted for approval. Shower heads & valves are based on Symmons, equals by Speakman may be submitted for approval.						
TYPE	FIXTURE	WASTE	VENT	COLD WATER	HOT WATER	DESCRIPTION
A	Water Closet	4"	2"	1"	-	Floor "New Madera" #F2222 Vit. China siphon jet action toilet w/elongated bowl, 1 1/4" top spud, 110 FTV Sloan Royal Valve, Olsonite 10-cc black open front seat.
B	Urinal	2"	1 1/2"	3/4"	-	24" to Lip "Washbrook" #F6500, vit. china washout urinal w/extended shields, integral flush spreader, 3/4" top spud, #186-11 Sloan Royal flush valve, wall hangers.
C	Lavatory	1 1/2"	1 1/2"	1/2"	-	30" to Lip "Regalyn" #4867 acid-resisting enameled cast iron lavatory, front overflow, wall hangers, #R2532 drain plug w/integral perforated grid, #R-7013-45 P-trap, #2604-1 supply with screw driver stop #R2212 self closing faucets.
D	Same as Type "C" except to have 1/2" hot water supply fitting and pop up drain #N2101-8.					
E	Drinking Fountain	1 1/2"	1 1/2"	1/2"	-	Wall Mount "Yukon" #P 8440-6 acid resisting enameled cast iron drinking fountain, enameled wall bracket, #R 60003-2 supply fitting with combination self-closing valve, manual volume regulator #R 7005-44 rough brass plate "P" trap with chrome escutcheon.
F	Shower Head #4-295L exposed inlet, tapped on left. Adjustable spray, adjustable volume control and vandal proof.					
G	Shower Head and Valve, same as Type "F" except bottom inlet and provide shower off "60" #4-425A exposed valve with integral stop and wall flange with anchor plates.					
H	Shower Head & Valve, same as Type "F" except bottom inlet and provide #4510A safety mix exposed valve with wall flange with anchor plate.					
FD-1	Floor Drain	3"	-	-	-	Floor #Z-415 triumph drain, cast iron floor drain with 7" nickel bronze strainer clamping collar, vandal proof screws with trap.
FD-2	Floor Drain	4"	-	-	-	Floor #Z-415 triumph drain, cast iron floor drain with 8" nickel bronze strainer clamping collar, vandal proof screws, w/trap.
DD-1	Drip Drain	2"	-	-	-	2'-0" From Floor #Z-325 cast iron drip drain with open top and interior dome strainer.
Thermostatic Water Controller: Furnish and install two Lawler Model 66-80, 1" inlet, 1 1/4" outlet, 80GPM. Assembly unit No. 66-2-0008 Thermostatic water controller, complete with integral check valves, thermometer and stops. Finish: polished chrome plate.						

SYMBOL LIST	
	Soil or waste pipe
	Soil or waste buried.
	Storm pipe
	Vent pipe
	Cold water pipe
	Hot water pipe
	Tempered supply water
	Gas pipe
	Gate valve
	Butterfly valve
	Angle valve
	Check valve
	Tee
	Pipe union
	Pressure relief valve
	Sillcock or Hose Bibb
	Thermometer
	Traps
	Cleanouts
	Cold water pipe
	Hot water pipe
	Hose bibb
	Sill cock
	Tempered Supply
	Recirculating inlets
	Backwater valve
	Floor drain
	Cleanout

