

REGRADE WALKWAY SUCH THAT STORM WATER IS DIVERTED FROM THE AREA TO BE EXCAVATED. THIS MUST BE DONE BEFORE ANY REGRADEING IS BEGUN. TO BE PAID FOR UNDER BID ITEM #1 EXCAVATION AND FORMATION OF EMBANKMENT.

SOD AREA

FOUL LINE

SKINNED AREA

SOD AREA

B.M. - ELEV. 60.07
SPIKE IN 42" RED OAK

PLAYERS BENCH

TO BE SALVAGED
BY CONTRACTOR AND
DELIVERED TO CITY
PARK DEPT. FACILITY
AS DIRECTED

BACKSTOP

PLAYERS BENCH

TEST PIT #1 8' DEEP
NO BEDROCK
NO WATER
SILTY CLAY MAT'L.

PROPOSED
SOFTBALL FIELD

PROPOSED
SOFTBALL FIELD

HAY BALE CHECKS

POND

EXIST. DEPRESSED M.H.
COVER WITH EARTH AND SOD OVER
TO MATCH SURROUNDING GRADE.

FOUL LINE

SKINNED AREA

SOD AREA

PLAYERS BENCH

BACKSTOP

CONTRACT LIMIT LIMIT

NOTE:

EXISTING UNDERGROUND STRUCTURES OR SERVICES ARE SHOWN IN AS NEAR THEIR CORRECT POSITION AS POSSIBLE. HOWEVER, ALL SUCH LOCATIONS ARE APPROXIMATE ONLY AND ALL SUCH STRUCTURES OR SERVICES MAY NOT BE SHOWN. CONTRACTOR IS TO ASCERTAIN THE LOCATION AND DEPTH OF ALL UNDERGROUND STRUCTURES AND SERVICES PRIOR TO EXCAVATION.

FUSS & O'NEILL
consulting engineers
MANCHESTER, CONNECTICUT

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

SITE PLAN
POPE PARK PLAYFIELD
PARK ST. & POPE PARK DR. - HARTFORD, CT.

SUBMITTED <i>[Signature]</i> DIVISION ENGINEER	RECOMMENDED <i>[Signature]</i> CHIEF OF ENG. SERV.	APPROVED ASST. DIR. & CITY ENG.
DRAWN S.L.F. CHECKED W.D.O.	SCALE 1" = 40'	DAYBOOK NO. 010765 DATE SEPT 17, 1981



REVISIONS
9-25-81

81-157 A