



NOTES

For concrete details see Sheet No.32
For bar type schedule see Sheet No.85 .
The minimum cover for main steel reinforcement is 3" except where concrete is poured against earth in which case it is 4".
Bar splices are equal in length to 40 diameters of the smaller bar.
Radius of bend of bars is equal to 4 diameters of the bar.
Payment for furnishing, bending, and placing of steel reinforcement was made under Item No.25

	12-31-45	As built revisions			
KEY	DATE	REVISION (Indicated by Δ)	REV. BY	CK. BY	AP. BY

CONNECTICUT RIVER FLOOD CONTROL
HARTFORD DIKE
 RIVERFRONT, MORGAN ST. TO STA. 96+73
WALL - STA. 21+76.19 TO STA. 22+09.36
STEEL REINFORCEMENT

CONNECTICUT RIVER CONNECTICUT
 IN 135 SHEETS SCALE: 1/4 IN. = 1 FT. SHEET NO. 98



U.S. ENGINEER OFFICE, PROVIDENCE, R.I., MAY 1940

SUBMITTED: *Harold A. Higgins* APPROVAL RECOMMENDED: *DeBussone* APPROVED: *W. H. Rogers*
 SENIOR ENGINEER PRINCIPAL ENGINEER AT. COL. CORPS OF ENGINEERS
 HEAD DESIGN SECTION CHIEF, F.C. ENGINEERING DIV. DISTRICT ENGINEER

DESIGNED: *W. H. Rogers* DRAWN: W. A. G. FISCAL YEAR 1940
 CHECKED: *W. H. Rogers* D.P. FILE NO. CT-4-2558