

LEGEND

NEW	EXISTING	DESCRIPTION
x 365.0	365.0	Elevations
x—F—x	x—EF—x	Fence
—	—	Tree line
—	—	Grade to drain
—	—	Stone wall
—	—	Limit of contractors work area
—E—	—E—	Electric line overhead
—T—	—T—	Telephone line overhead
—	—	Earth cut and rock cut
—	—	Earth fill
—	—	Earth fill with rock slope protection
—	—	Earth surface (Section)
—	—	Assumed rock surface or rock cut (Section)
—	—	Approximate limits of excavation
—NSD—	—SD—	Storm drain
—D.I.	—	Drain inlet
—NS5—	—SS—	Sanitary sewer
—DMH	—DMH	Drain manhole
—NW—	—EW—	Water line
—	—G—	Gas line
—	—CB	Catch basin
—	—SMH	Sanitary manhole
—	—	Gate valve
—	—	Pole
—	—	Manhole
—	—	Greater Hartford Flood Commission Boring (1960-1963)
—	—	Flood Commission Boring (1960)
—	—	Connecticut Highway Department (1959)
—	—	U.S. Army Corps of Engineers Boring
—	—	Seismic Line
—	—	Driving Test Pile Location
—	—	Driving Test Pile and Load Test Location

CONT'D.

NEW	EXISTING	DESCRIPTION
28A-2		Pressure Manhole
		Plant Identity Key and Quantity (See Specifications)
		Tree
		Deciduous tree
		Evergreen tree
		Shrub

VICINITY MAP
SCALE 1"=3.5 MILES

GENERAL NOTES:

1. Elevations refer to Mean Sea Level Datum.
2. All elevations are plus except as noted otherwise.
3. Plane coordinates refer to Connecticut Lambert Grid System.
4. Figures in hexagons indicate item numbers under which payment will be made.
5. Bid item references are shown on the drawings for convenience only. Under no circumstances should these items be used without reference to the specifications which describe the work and bid item. Should there be any discrepancies between the work covered by the bid item numbers as shown on the drawings and in the specification, the specifications shall govern.
6. For control see sheet 3.
7. For record of explorations see Division II of specifications.

PLAN
SCALE: 1"=200'GRAPHIC SCALES
1"=200' 0 200' 400'

As Built Drawing

Contract No. DACW 33-76-C-0098

VALUE
ENGINEERING
PAYS
DIVIDENDS

REVISION	DATE	DESCRIPTION	BY
DEPARTMENT OF THE ARMY NEW ENGLAND DIVISION CORPS OF ENGINEERS WALTHAM, MASS.			
WATER RESOURCES DEVELOPMENT PROJECT PARK RIVER LOCAL PROTECTION			
GENERAL PLAN			
HARTFORD		CONNECTICUT	
APPROVED		DATE MARCH 1976	
SCALE 1"=200'		SPEC. NO. DACW 33-76-B-0040	
DRAWING NUMBER		PAR-1	
SHEET 2			