

STATION 3182

QUADRANGLE Hartford

FILE NO.

CONNECTICUT GEODETIC SURVEY  
FORM NO. C.G.S. 12

TOWN Windsor

COUNTY Hartford

DATE Feb. 29, 1960

COMPUTATION VOL.

" DATE

DISTANCES AND DIRECTIONS TO REFERENCE MARKS						PLANE AZIMUTH		
OBJECT	DISTANCE FT.	DIRECTION						
Mon. #3189	597.73	0	00	00	0	23	33	27.7
R.M.#1	163.96	105	56	05				
R.M.#2	22.87	343	06	48				
R.M.#3	229.16	359	52	35				

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 3182 and set in the top of a reinforced concrete post, the top flush with the ground.

Plane Coordinates (Feet)

x = 624,254.93

y = 352,926.38

Elevation (mean sea level datum)

Feet:

Meters:

Station is on the west side of Windsor Avenue (Windsor-Hartford Rd.) 229' north of the Windsor-Hartford Town Line and about 800' south of the Windsor Expressway overpass. Station is about on the north range of Sunset St., 4.3' west of the concrete sidewalk, and 57.78' south of HELT pole #1946.

R.M.#1: Northwest of station: Southeast corner of concrete foundation of rear part of building #15.

R.M.#2: South of station: Small drill hole in west side of rim of manhole in sidewalk.

R.M.#3: South of station: Small hole in lead plug of 6x6 granite monument on the Windsor-Hartford Town Line. Monument is 3.8' west of the sidewalk.

Fuller tie revised because of tape calibration

6/20/60

