

STATION 2686

QUADRANGLE

HARTFORD

FILE NO.

CONNECTICUT GEODETIC SURVEY
NEW HAVEN, CONN.

TOWN HARTFORD
 COUNTY HARTFORD
 DATE MAY 7, 1940
 COMPUTATION VOL. 108
 " DATE

DISTANCES AND DIRECTIONS TO REFERENCE MARKS							
OBJECT	DISTANCE FT.	DIRECTION			PLANE AZIMUTH		
MON. 2685X	1082.39	0	00'	00	194	54	59.8
R.M. 1	27.58	101	32	40			
R.M. 2	24.88	220	10	20			
R.M. 3	102.92	320	56	20			

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 2686, SET IN THE TOP OF A REINFORCED CONCRETE POST, THE TOP FLUSH WITH THE GROUND. THE STATION IS AT THE INTERSECTION OF WESTBOURNE PARKWAY AND U.S. #44 (ALBANY AVENUE), 0.65 MILE SOUTHEAST ALONG U.S. #44 FROM THE HARTFORD-WEST HARTFORD TOWN LINE. IT IS IN THE ESPLANADE ON THE WESTBOURNE PARKWAY, 16 FEET WEST OF THE CENTER-LINE OF THE EAST LANE OF THE PARKWAY, AND 24 FEET NORTHEAST OF IRON POLE #K-26.

R.M. 1: SOUTHEAST OF STATION: A DRILL HOLE IN A TRIANGLE ON A CONCRETE CURB, 12 FEET EAST OF THE CENTER-LINE OF THE EAST LANE OF A PARKWAY, 4 FEET NORTHWEST OF THE WEST EDGE OF A CONCRETE WALK ABOUT 13 FEET NORTH OF THE SOUTH END OF THE CURB.

R.M. 2: SOUTHWEST OF STATION: THE NORTHEAST CORNER OF A FIRE ALARM BOX AT THE END OF THE ESPLANADE.

R.M. 3: NORTH OF STATION: THE NORTHEAST CORNER OF A CONCRETE FOUNDATION AT #1530 ALBANY AVENUE OCCUPIED BY THE FIRST NATIONAL STORE.

Plane Coordinates (Feet)

X= 612,729.94

Y= 346,541.77

Elevation (mean sea level datum)

Feet: 72.038

Meters: 21.9571

January 20, 1960