

STATION 2685X

QUADRANGLE Hartford

FILE NO.

CONNECTICUT GEODETIC SURVEY
NEW HAVEN, CONN.

DISTANCES AND DIRECTIONS TO REFERENCE MARKS								
OBJECT	DISTANCE FT.	DIRECTION			PLANE AZIMUTH			
Mon. 2686	1082.39	°	'	"	°	'	"	
R.M. 1	69.13	0	00	00	14	54	59.8	
R.M. 2	45.55	70	09	40				
R.M. 3	62.23	156	09	40				
		277	10	20				

TOWN Hartford

COUNTY Hartford

DATE May 7, 1940

COMPUTATION VOL.

" DATE

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 2685X, set in the top of a reinforced concrete post, the top flush with the ground.

Plane Coordinates (Feet)

Elevation (mean sea level datum)

x= 613,008.56

Feet: 62.875*

y= 347,587.68

Meters: 19.1642

The station is on the northwest side of Westbourne Parkway at its intersection with Garfield Street, 0.10 mile west of Blue Hills Avenue, and 0.20 mile northeast of U.S. #44 (Albany Avenue). It is at the northeast corner of the intersection, 18 feet east of the center-line of Garfield Street, 45 feet northeast of the center-line of Westbourne Parkway, 46 feet northeast of H.E. Lt. Co. pole #1647, and 10 inches west of the intersection of the sidewalks.

R.M. 1: West of station; The southeast corner of a concrete foundation of #83 and #85 Westbourne Parkway.

*Mont. lowered 0.165 April 26, 1944

R.M. 2: North of station; The southwest corner (front) of a concrete foundation of #91 and #93 Westbourne Parkway. Revised elevation =62.710

R.M. 3: Southeast of station; The top center of a hydrant in the esplanade opposite 91-93 Westbourne Parkway.

January 20, 1960