

STATION 2684

QUADRANGLE Hartford

FILE NO.

CONNECTICUT GEODETIC SURVEY  
NEW HAVEN, CONN.

TOWN Hartford

COUNTY Hartford

DATE May 7, 1940

COMPUTATION VOL.

" DATE

## DISTANCES AND DIRECTIONS TO REFERENCE MARKS

OBJECT	DISTANCE FT.	DIRECTION	PLANE AZIMUTH
Mon. #2683	1111.41	0° 00' 00"	196° 31' 06.3"
R.M. # 1	178.94	20 35 40	
R.M. # 2	14.23	192 59 20	
R.M. # 3	30.19	236 58 20	

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 2684, set in the top of a reinforced concrete post, the top flush with the ground.

The station is on the southeast side of Blue Hills Avenue 0.60 mile south of the Hartford-Bloomfield town line, or 0.85 mile north of the intersection of Westbourne Parkway and Blue Hills Avenue. It is 24 feet southeast of the center-line of Blue Hills Avenue, 44 feet west of H.E. Lt. Co. pole #7424 on the opposite side of the street and 6 inches west of the west edge of the sidewalk.

R.M. # 1: Northeast of station: The southwest corner (front) of a concrete foundation of the building at #450 and #452 Blue Hills Avenue.

R.M. # 2: Southwest of station: The northwest corner of an iron grating of a catch basin, 19 feet southeast of the highway center-line.

R.M. # 3: West of station: The center of a circular manhole cover directly opposite Westminster Street.

Plane Coordinates (Feet)

x = 614,637.23

y = 351,337.97

Elevation (mean sea level datum)

Feet: 144.707\*

Meters: 44.1068

\*Mont. lowered 0.33 April 26, 19-

Revised elevation = 144.377

44

XXXXXXXXXXXXXXXXXXXX  
January 20, 1960

July 1, 1960

4-76-7