

STATION 2688

QUADRANGLE Hartford

FILE NO.

✓ CONNECTICUT GEODETIC SURVEY
NEW HAVEN, CONN.

TOWN Hartford
 COUNTY Hartford
 DATE May 9, 1940
 COMPUTATION VOL. 108
 " DATE

DISTANCES AND DIRECTIONS TO REFERENCE MARKS							
OBJECT	DISTANCE FT.	DIRECTION			PLANE AZIMUTH		
Mon. 2689	533.69	0°	00'	00"	90°	03'	55.8"
R.M. 1	24.16	32	59	40			
R.M. 2	58.35	221	33	40			
R.M. 3	58.14	322	05	20			

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 2688, set in the top of a reinforced concrete post, the top flush with the ground.

Plane Coordinates (Feet)

Elevation (mean sea level datum)

x= 609,926.72

Feet: 107.052

y= 347,480.62

Meters: 32.6295

The station is on the northeast side of U.S. #44 (Albany Avenue) and Conn. #9 (Bloomfield Avenue), 97 feet east of the traffic rotary at their intersection in Hartford. It is between the curb and a concrete walk, 3.15 feet northeast of the face of the curb on Albany Avenue, 1.95 feet southwest edge of walk, 34 feet southeast of H.E. Lt. Co. pole #7776, and 34 feet northeast of the center-line of Albany Avenue.

R.M. 1: Northwest of station; The southeast corner of a square Gas Co., curb box, 11 feet east of the H.E. Lt. Co. Pole #7776, and 3 feet north of curb.

R.M. 2: Southeast of station; The northwest corner of square H.E. Lt. Co. manhole cover, 92 feet east of H.E. Lt. Co. pole #7776, and 9 feet south of north curb.

R.M. 3: Southwest of station; The center of a circular manhole cover, 22 feet north of H.E. Lt. Co. pole #9181, and 23 feet north of catch basin on south edge of Albany Avenue.

January 20, 1960

022-25