

STATION NO.: 2608
TOWN: Hartford
COUNTY: Hartford
DATE: Mar. 8, 1940

| OBJECT | DIST. FT. | DIRECTION | PLANE AZIMUTH |
|------------|-----------|-----------|---------------|
| Mon. #2609 | 744.88 | 0 00 00 | 0 150 48 49.8 |
| R.M. #1 | 58.76 | 44 05 00 | |
| R.M. #2 | 43.00 | 160 40 00 | |
| R.M. #3 | 7.80 | 229 11 00 | |

STATION MARK IS U.S.C. & G.S. & STATE SURVEY BRONZE DISK
STAMPED: 2608, set in the top of a reinforced concrete
post, the top flush with the ground.

The station is on the east side of Conn. #9, opposite its
intersection with Victoria Road, 173 feet north of the
Wethersfield-Hartford town line, and 100 feet northeast
of the traffic rotary. It is between the curb and the
sidewalk, 0.7 foot west of the west edge of the walk,
and 1.1 feet east of the curb.

R.M. #1: Northeast of station: The southwest corner of
a small building marked Tourist's Information Bureau,
on the east side of Conn. #9.

R.M. #2: Southeast of station: The top of the northwest
corner of the concrete wall on the north side of the con-
crete steps leading to the house at #1010 Wethersfield
Avenue.

R.M. #3: Southwest of station: The center of a circular
cast iron manhole, marked H.E.L. Co., on the east side
of Conn. #9, and opposite Victoria Road.

| PLANE COORDINATES (FEET) | ELEVATION FEET: METERS: |
|------------------------------|-------------------------------|
| X 622,168.58 Y 326,233.43 | |

