

STATION 2600

QUADRANGLE Hartford

FILE NO.

CONNECTICUT GEODETIC SURVEY
NEW HAVEN, CONN.

TOWN Hartford
COUNTY Hartford
DATE May 9, 1940
COMPUTATION VOL. 108
" DATE

DISTANCES AND DIRECTIONS TO REFERENCE MARKS			
OBJECT	DISTANCE FT.	DIRECTION	PLANE AZIMUTH
Mon. 2688	641.03	0° 00' 00"	335° 05' 41.4"
R.M. 1	45.23	86° 47' 00"	
R.M. 2	22.21	148° 00' 00"	
R.M. 3	113.23	228° 08' 20"	

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 2600, set in the top of a reinforced concrete post, the top set about 1 inch below the ground.

Plane Coordinates (Feet)

Elevation (mean sea level datum)

x= 609,656.77

Feet: 110.105

y= 348,062.04

Meters: 33.5601

The station is on the east side of Conn. #9 (Bloomfield Avenue), about 0.10 mile north of its intersection with U.S. #44. It is in a grass strip between sidewalk and a gutter between H.E.Lt. Co. poles #5735 and #5736 on the opposite side of the highway, 7 inches west of the west edge of the sidewalk, and 21 feet east of the highway centerline.

R.M. 1: West of station: The top center of a hydrant on the west side of the highway between H.E.Lt. Co. poles #5735 and #5736.

R.M. 2: Northwest of station: The center of a manhole cover on the easterly side of the highway, 74 feet northeast of H.E. Lt. Co. pole #5735, and 49 feet southeast of pole #5736.

R.M. #3: Northeast of station: The southeast corner of the foundation of a house at #56 Bloomfield Avenue, on the east side of the highway.

January 20, 1960