

STATION . 934 .

QUADRANGLE

Hartford

FILE NO.

CONNECTICUT GEODETIC SURVEY
NEW HAVEN, CONN. ✓

TOWN Hartford
 COUNTY Hartford
 DATE July 13, 1940
 COMPUTATION VOL. 101
 " DATE

DISTANCES AND DIRECTIONS TO REFERENCE MARKS								
OBJECT	DISTANCE FT.	DIRECTION			PLANE AZIMUTH			
Tower of Travelers Ins. Building	4246.62	0	00	00	135	46	01.1	
R.M. 1	109.35	06	07	00				
R.M. 2	68.63	257	40	00				
R.M. 3	67.12	284	26	40				

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 934, set in the top of a reinforced concrete post, the top set flush with the ground.

Plane Coordinates (Feet)

Elevation (mean sea level datum)

X=623,916.68 ✓

Feet:

Y=336,198.06 ✓

Meters:

The station is on the east side of Van Dyke St., in Hartford between Masseek and Sequassen Streets, and west of the city dump. It is on the top of the river dike opposite Colts factory, 20 feet east of the east rail of the railroad track, 10 feet east of the power line pole, and 21.5 feet south of the south range of a 4-storied building owned by Colts.

R.M. #1: Northwest of station; The southeast corner of a 7-foot square brick structure projecting 2 feet above the ground, located on the top of the dike.

R.M. #2: Southwest of station; The southeast corner of a concrete wall on the west side of the sidewalk, and 40.5 feet south of the south range of a 4-storied building owned by Colts.

R.M. #3: West of station; The northeast corner of the same wall mentioned in R.M. #2, and 8 feet south of the south range of the same building also mentioned in R.M. #2.