

Not found Apr '60

STATION 933

QUADRANGLE

Hartford

FILE NO.

CONNECTICUT GEODETIC SURVEY
NEW HAVEN, CONN.

TOWN Hartford
 COUNTY Hartford
 DATE Jan. 21, 1940
 COMPUTATION VOL. 101
 " DATE

DISTANCES AND DIRECTIONS TO REFERENCE MARKS							
OBJECT	DISTANCE FT.	DIRECTION			PLANE AZIMUTH		
Pratt & Whitney Tank	5828.52	0	00	00	281	27	21.1
R.M. 1	52.50	11	57	00			
R.M. 2	97.40	162	44	00			
R.M. 3	117.10	223	37	00			
R.M. 4	53.42	277	43	00			

Station Mark is U. S. C. and G. S. State Survey Bronze Disk Stamped: 933, set in the top of a reinforced concrete post, the top 2 inches below the ground.

Plane Coordinates (Feet)

Elevation (mean sea level datum)

x= 624,910.47 ✓

Feet:

y= 334,872.10 ✓

Meters:

The station is on the south side of Warwarme Avenue between Aviation Road and Van Dyke Avenue in Hartford. It is on the top of a 10-foot bank about 70 feet southwest of H.E. L.T. Co. pole #4726, and 74 feet southeast of the center-line of the intersection of Warwarme Avenue and Aviation Road.

R.M. 1: Southeast of station; The northwest leg of the high tension line tower.

R.M. 2: West of station; The top of a square concrete post with 3-foot projection marked H.W.W. 1927 on south side of Warwarme Avenue, and about 7.6 feet north of S.N.E.T. Co. pole #1634.

R.M. 3: North of station; The top of a hydrant on the north side of Warwarme Avenue, and 47 feet southwest of the H.E.L. Co. pole #7602.

R.M. 4: Northeast of station; The spike in a C.C.S. concrete marker, 18 feet south of H.E.L. Co. pole #4727.