

CITY OF HARTFORD, CONNECTICUT

HARTFORD MUNICIPAL AIRPORT

SUMMARY OF QUANTITIES OF MAJOR ITEMS				
ITEM		QUANTITIES		
EXCAVATION FOR PAVEMENT		22,000	CU. YDS.	
PAVING		73,200	SQ. YDS.	
PIPE FOR STORM DRAINAGE LINES		CONCRETE OR CORRUGATED		
6" DIAM.		540	LIN. FT.	
8" DIAM.		847 307	LIN. FT.	
10" DIAM.		825 825	LIN. FT.	
12" DIAM.		397 397	LIN. FT.	
15" DIAM.		1,615 825	LIN. FT.	
18" DIAM.		1,470 1,540	LIN. FT.	
21" DIAM.		1,357 1,577	LIN. FT.	
24" DIAM.		240 925	LIN. FT.	
MANHOLES		33		
CATCH BASINS		32		
EXCAVATION FOR DRAINS		2,950	CU. YDS.	
GRADING, SEEDING, MARKINGS, ETC.			LUMP SUM	
UNDERGROUND DUCTS		1,400	LIN. FT.	
LIGHTING				
ELEVATED RUNWAY MARKER LIGHTS		39		
THRESHOLD LIGHTS		12		
FLUSH CONTACT LIGHTS RESET		1		
THRESHOLD LIGHTS RESET		4		
OBSTRUCTION LIGHTS RESET		1		
UNDERGROUND CABLE		15,000	LIN. FT.	
BOUNDARY LIGHTS RESET		2		
ADD TO QUANTITY OF PIPE		CONCRETE OR CORRUGATED		
24" DIAM. (HEAVY REINFORCED)		355	LIN. FT.	
27" DIAM.		835 170	LIN. FT.	
30" DIAM.		240 1,075	LIN. FT.	

INDEX TO DRAWINGS	
TITLE	SHEET NO.
TITLE AND APPROVAL SHEET	1
INDEX AND SUMMARY OF MAJOR ITEMS	2
LOCATION MAP	3
MASTER PLAN	4
LAYOUT PLAN & PROFILE	5
LOG OF BORINGS	6
DRAINAGE PLAN	7
STORM DRAINAGE PROFILES - LINES A,B,C,F.	8
STORM DRAINAGE PROFILES - LINES D,E.	9
DRAINAGE DESIGN COMPUTATION	10
DRAINAGE DETAILS	11
PAVING PLAN	12
INTERSECTION DETAILS	13
LIGHTING LAYOUT	14
ELECTRICAL DETAILS	15
ELECTRICAL DETAILS	16
CONSTRUCTION PROJECT SIGN FOR FEDERAL AID AIRPORTS	17
EXHIBIT A	18