

Mar. 28-29		A	16-30	5-40 P.M.	0.83	0.05	3-20	5-00 A.M. of the 29th.	0.1	20	0.15	0.15	0.15	0.12
" " "		C	16-00	5-30 "	1.00	0.06	5-00	5-30 " " "	0.1	20	0.3	0.30	0.30	0.20
Apr. 6-10		A	58-00	10-00 P.M.	1.58	0.02	2-20	4-40 P.M. " " 9th	0.23	15	1.08	1.08	0.90	0.64
" 29-30		A	13-00	9-00 P.M.	1.87	0.13	8-00	10-30 P.M. of the 29th	0.17	30	0.4	0.4	0.4	0.4
" " "		B	12-30	" " "	1.90	0.15	"	11-00 " " "	0.18	50	0.45	0.45	0.45	0.45
" " "		C	11-45	" " "	1.88	0.16	"	" " " " " "	0.17	10	0.50	0.50	0.45	0.40
Jun. 3-4		A	4-00	4-30 P.M.	0.76	0.19	1-00	4-25 P.M. " " 3d	0.65	10	2.48	2.48	1.60	1.06
" 15	TS	A	1-00	6-20 A.M.	0.53	0.53	0-15	7-05 A.M.	2.0	15	2.00	2.00	1.50	1.00
" 16	TS	C	11-00	1-35 P.M.	1.04	0.09	0-35	1-35 P.M.	1.20	35	1.20	1.20	1.20	1.20
" 29		C	11-00	9-00 A.M.	0.95	0.08	6-00	1-30 P.M.	0.12	20	0.4	0.4	0.4	0.3
July 5		B	14-00	8-15 P.M.	1.10	0.08	1-30	8-15 P.M.	0.5	15	1.90	1.90	1.50	1.00
" 15	TS	A	4-00	2-50 P.M.	1.31	0.33	0-35	6-25 P.M.	1.31	35	1.31	1.31	1.31	1.31
" " "		C	7-30	3-00 "	1.27	0.17	0-50	3-05 "	1.26	30	1.70	1.70	1.70	1.70
" 19-20	TS	A	42-00	5-20 A.M.	1.52	0.03	2-00	9-15 P.M. of the 20th	0.37	30	0.7	0.7	0.7	0.7
" 22	TS	C	1-00	5-30 P.M.	0.73	0.73	0-30	5-30 P.M.	1.40	10	3.30	3.30	1.95	1.40
Aug. 11	S	A	19-00	12-20 A.M.	3.26	0.17	3-00	9-00 A.M.	0.55	20	1.20	1.20	1.20	0.90
" " "		C	"	" " "	2.39	0.12	1-40	12-20 "	0.48	20	1.05	1.05	1.05	0.80
Sept. 4	TS	A	11-00	3-40 A.M.	0.90	0.08	0-20	4-50 A.M.	1.65	20	1.65	1.65	1.65	1.15
" 9		A	8-00	1-40 P.M.	1.85	0.23	5-00	1-50 P.M.	0.33	10	1.50	1.50	1.00	1.00
" " "		C	9-30	1-30 "	1.59	0.16	5-30	1-30 "	0.26	40	0.9	0.9	0.9	0.9
" 28	TS	C	1-30	7-00 P.M.	0.98	0.65	1-30	7-00 P.M.	0.65	40	1.05	1.05	1.05	1.05
Oct. 5		A	15-00	12-01 P.M.	1.27	0.08	3-00	12-01 A.M. of the 6th.	0.2	60	0.25	0.25	0.25	0.25
" " "		C	"	11-00 A.M.	1.36	0.07	"	10-30 P.M.	0.22	30	0.2	0.2	0.2	0.2
" 11		A	12-00	6-00 P.M.	1.72	0.14	12-00	6-00 "	0.14	40	0.6	0.6	0.6	0.6
" 27	S	A	12-00	11-30 P.M.	3.42	0.28	11-00	11-30 P.M.	0.30	20	1.35	1.35	1.35	1.00
" " "		C	11-00	" " "	3.44	0.31	10-00	" " "	0.33	90	0.52	1.20	0.84	0.60
Nov. 26		A	11-00	2-00 A.M.	0.70	0.06	5-00	6-00 P.M.	0.1	30	0.2	0.2	0.2	0.2
Dec. 5	*	A	10-00	3-30 A.M.	0.75	0.07	10-00	3-30 A.M.	0.07	30	0.2	0.2	0.2	0.2
" 13	*	A	22-00	2-00 A.M.	0.94	0.04	7-00	2-00 P.M.	0.08	60	0.15	0.15	0.15	0.15
" 16		A	22-00	2-00 A.M.	1.80	0.08	22-00	2-00 A.M.	0.08	30	0.4	0.4	0.4	0.4
" 21	S	A	13-30	1-30 P.M.	2.37	0.17	5-30	9-30 P.M.	0.31	180	0.37	0.4	0.4	0.4

Abbreviations:-

TS Thunderstorm, * Rain and Snow, * Snow, @ Rain preceded by Ice Storm, S Storms which surcharged the Franklin Ave. Sewer.
A City Hall, B New Britain and Fairfield Avenues, C Wetherstfield Ave. and Jordan Lane.

Rates of Precipitation, in all cases, are given in inches and decimal parts of an inch per hour.

In the above table no storms have been included which precipitated less than one half inch. Storms omitted have occurred as follows: from July 1 to Dec. 31, 1900, 40 storms; from Jan. 1, to Dec. 31, 1901, 43 storms; from Jan. 1, to Dec. 31, 1902 49 Storms.

Total number of storms precipitating over one half inch, included in above table, 71
Total number of small storms during same period, omitted from above table, 132
Total number of storms from July 1, 1900, to Dec. 31, 1902. 203.