

SPECIFICATIONS FOR CABINET IN VAULT  
OF BOARD OF STREET COMMISSIONERS.

---

The Contractor is to remove all the woodwork now in the brick vault of the Board of Street Commissioners before building the new cabinet.

The cabinet in general and detailed plan is shown on blue print and all necessary dimensions given.

The best quality of selected quarter sawn oak is to be used for all exposed finished surfaces. All other wood used to be selected white wood. All drawers to run on splines made of the best maple stock.

All drawers of the same size to be interchangeable and to run smoothly without slipping sideways. Drawers to be finished inside and out with shellac, and care taken that the bottom of each drawer is so adjusted as not to interfere by sagging with the next lower drawer. The two upper six inch drawers to have lock and key to correspond with hardware specified later. All drawers to have joints on all sides of front. Drawer pulls and handles for sliding doors to be of brass like sample. The panels for sliding wood doors to be framed out of solid stock.

For all sliding doors Contractor is to furnish proper brass track and sheaves.

All exposed surfaces to be filled and finished by a sufficient number of coats of shellac, well rubbed, to secure a smooth, dull light colored natural finish to correspond with the finish on the sample "Long Document File" to be seen at the office of the Board of Street Commissioners.

In the lower compartment, a vertical partition is to be placed back of the vertical framework of each sliding door. In the upper compartment used for filing books, there are to be provided twenty spaces, two inches in the clear, two spaces five inches in the clear, the remainder of distance to be divided into spaces three inches in the clear. The partitions separating these compartments to be  $1/2$