

inch thick with oak facing. The two 3 inch spaces to be placed opposite the door in the vault.

All stock used in the case to be thoroughly dried by baking at least two weeks before being used.

All parts to be made in a thorough workmanlike manner, securely framed, and to the entire satisfaction of the Clerk of the Board of Street Commissioners.

The Contractor to guarantee the cabinet for one year from date of final acceptance of work, and adjust or alter any parts to secure a free, easy working of the cabinet during that period without any additional compensation.

Contractors are requested to visit the vault and satisfy themselves of the conditions relative to the work.

Only one cabinet is wanted.

All parts of this cabinet must pass through a doorway twenty one inches by five feet in a brick wall twenty-one inches thick.

*Mail bid in lump sum to
Mr. George News, Clerk of Board of
Street Commissioners, in time for him to
receive them by 5 P. M. Wed. Feb. 21st.*