

Curves for Center Line of New Britain Ave.

Scale 1"=40'

Curb Lines to be parallel
with R.R. Track.

Curve near Sta 7000

$R = 4583.75$
 $I = 4^\circ - 15'$
 $\frac{I}{2} = 2^\circ - 7.5'$
 Tangents 170.10
 Def. for 100' $0^\circ - 37.5'$
 Def. for 50' $0^\circ - 18.75'$
 Def. for 50' chords
 $0^\circ - 19'$
 $0^\circ - 38'$
 $0^\circ - 56'$
 $1^\circ - 15'$
 $1^\circ - 34'$
 $1^\circ - 53'$
 $2^\circ - 7.5'$

