

9 BAYS @ 60' EA = 540'



NEW BORING
(REFER TO GRID LINES FOR NAME -
THUS - A1)

NEW BORINGS TO BE CORED
WILL INDICATE ONE OR THE
OTHER OF THESE TWO
NOTATIONS
(WHERE MARKED "TO REF. ONLY"
DO NOT CORE)

90.0 BORINGS INCLUDING CORE MUST
BE CARRIED AT LEAST TO THIS
ELEVATION (SEE NOTE BELOW RE:*)
CORE 20' MINIMUM LENGTH OF CORE
REQUIRED INTO ROCK

Diagram illustrating the components of a wellpoint symbol:

- WELLPOINT**: Points to the symbol.
- EL 90.0**: Points to the elevation value.
- BORING IN WHICH WELLPOINT IS TO BE INSTALLED AFTER**: Points to the symbol.
- ELEVATION AT WHICH WELLPOINT IS TO BE INSTALLED**: Points to the elevation value.


 No 39 ← BORINGS MADE BY GENERAL
 BORINGS INC., STRAITSVILLE RD
 PROSPECT, CONN.
 IN MARCH & APRIL 1969

* WHERE ASTERISK (*) OCCURS ROCK CORING SHALL BE NOT LESS THAN 5'-0"

* * WHERE DOUBLE ASTERISK (**) OCCURS ROCK CORING SHALL BE NOT LESS THAN 10'-0"

NOTE:
OUTLINE OF PROPOSED
BLDG SCHEMATIC
ONLY

1. WHERE EXISTING BUILDINGS OCCUR AT LOCATIONS SHOWN FOR BORINGS ENGINEER SHALL INSTRUCT DRILLER AS TO TEMPORARY OMISSION OF GUGH BORINGS FROM THE CONTRACT. IT IS NOT INTENDED THAT BORINGS SHALL BE TAKEN WITHIN EXISTING CONSTRUCTION.
2. BORINGS SHALL BE TAKEN IN ACCORDANCE WITH THE "KEY" ABOVE, AND THE SPECIFICATION.
3. ALL BORINGS SHALL BE STANDARD DRY SAMPLE BORINGS.
4. ALL ROCK CORING SHALL BE SERIES BX (15" DIAMETER) BORINGS.
5. WATER SHALL BE RECORDED WHERE ENCOUNTERED, IN ADDITION, WHERE INDICATED THIS ON PLAN OF WELLPOINT A WELLPOINT SHALL BE PERMANENTLY INSTALLED IN ACCORDANCE WITH THE PROVISIONS OF THE SPECIFICATION. (SEE KEY ABOVE)
6. SEE SPECIFICATION FOR COORDINATION OF BORING LOCATIONS WITH EXISTING UNDERGROUND UTILITIES.
7. SEQUENCE OF TAKING BORINGS SHALL BE IN THE PATTERN SHOWN. BORINGS NOT INCLUDED IN A SEQUENCE SHALL BE MADE AFTER OTHERS ARE COMPLETED.

SCALE 1" = 40'

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF ENGINEERING

BORING LOCATION PLAN
HARTFORD CIVIC CENTER
HARTFORD CONNECTICUT

B-1

SUBMITTED	BY	DATE
	Walter H. Pearl	George E. Neffman

DISPATCHED BY AIR MAIL
FRACILE

DAYTON 0010220
DATE OCTOBER 27 1970