



1. SEWER TO BE CONSTRUCTED UNDER A DEVELOPER'S PERMIT-
COMMITMENT BETWEEN THE CITY OF HARTFORD AND THE METRO-
POLITAN DISTRICT AND SHALL BE BUILT BY A LICENSED
SEWER DRAIN LAYER UNDER PERMIT ISSUED BY, AND UNDER
THE SUPERVISION OF, THE CHIEF ENGINEER OF THE BUREAU
OF PUBLIC WORKS.
2. STORM DRAIN SHALL BE USED FOR STORM DRAINAGE ONLY.
ALL STORM WATER COOLING WATER SURFACE AND SUB-SUR-
FACE DRAINAGE SHALL BE CONNECTED TO THIS DRAIN AS
APPROVED BY THE DISTRICT. ALL SANITARY WASTES AND
INDUSTRIAL WASTES ARE EXCLUDED BY DISTRICT ORDINAN-
CES.
3. BACKFILL IN TRENCHES IN TRAVELED WAYS OR UNDER
AREAS TO BE PAVED, OR WALKS, SHALL BE OF BANK-RUN
GRAVEL, SAND OR ACCEPTABLE NATURAL SOIL SATISFAC-
TORY TO TOWN, CITY OR STATE. TEMPORARY & PERMA-
NENT PAVING REPAIRS TO EXISTING PAVEMENT SHALL BE
MADE ACCORDING TO DISTRICT, TOWN OR STATE SPECI-
FICATIONS.
4. INSTALL ALL LATERALS AT MINIMUM 1.0% GRADE. LATER-
ALS TO THE CATCH BASIN SHALL BE BUILT BY THE
DEVELOPER IN CONJUNCTION WITH THE MAIN SEWER
CONSTRUCTION.
5. PIPE DESIGNATIONS:

C 76	ASTM C 76	Reinforced Concrete Pipe Class IV
D 3033	ASTM D 3033	Type PSP POLY (vinylchloride) (PVC) Sewer and Drain Pipe
6. ELEVATIONS REFER TO THE METROPOLITAN DISTRICT
DATUM.
7. JOB CODE: BROOKFIELD STORM DRAIN.

