

ELLIOTT STREET EAST
Wethersfield Ave To Ledyard St.
Storm Water Drainage Revisions

SUBMITTED	RECOMMENDED	APPROVED
<i>Raymond Bayne</i>	<i>Russell E. Long</i>	<i>David F. Sullivan</i>
DRAWN: SB	SCALE: H. 1"=40'	DAYBOOK NO. 010492 A'
CHECKED: RSIA	V. 1"=10'	DATE: OCTOBER 1974

GENERAL NOTES

1. Sewer to be constructed under a developer's permit-agreement between the City of Hartford and the Metropolitan District, and shall be built by a licensed drain layer under permit issued by, and under the supervision of, the chief engineer of the Bureau of Public Works.
2. Backfill in trenches in traveled ways or under areas to be paved, or walks, shall be of bank-run gravel, sand or acceptable natural soil satisfactory to the City of Hartford. Temporary and permanent paving repairs to existing pavement shall be made according to City of Hartford Specifications.
3. Storm drain shall be used for storm drainage only. All storm water, cooling water, surface and sub-surface drainage shall be connected to this drain as approved by the District. All sanitary wastes and industrial wastes are excluded by District Ordinances.
4. Install all laterals at minimum 1.0% grade. Laterals to the catch basins shall be built by the developer in conjunction with the main sewer construction.
5. Pipe Designations:
C76 ASTM C76 Reinforced concrete Pipe Class IV
D3033 ASTM D3033 Type PSF Poly (vinylchloride) (PVC) Sewer and Drain Pipe
6. Elevations Refer to the Metropolitan District Datum
7. See Plan and Profile of Elliott Street East.
(Daybook No. 010456) and plan and profile of Ledyard Street (Wawame Ave. to Elliott St. east) (Daybook No. 010452) for horizontal and vertical control.
8. All catch basins, manholes to be in accordance with Metropolitan District-Bureau of Public Works Standards.
9. All pipe to be abandoned shall be salvaged and become the property of the City of Hartford. The said City of Hartford shall be responsible to remove the pipe from the site.
10. The City of Hartford is aware that the use of the existing 36" Ø ROP storm lateral installed under MDC permit #67899 2-24-72 is depended on inspection and approval of its use by the MDC.
11. JOB CODE: Elliott Street East-Ledyard Street Storm Drains-Hartford
12. Contractor's attention is called to the requirement that all existing storm water flows must be maintained at all times during construction. All storm sewers to be abandoned are to be done only after the new system is operational.