


CITY OF HARTFORD
DEPT. OF ENGINEERING-

CITY OF HARTFORD

DEPT OF ENGINEERING-



CENTRAL ROW

NOTES

ALL DIMENSIONS SHOWN ARE APPROX. & MUST BE VERIFIED AT THE JOB BY CONTRACTOR. BROWNSTONE COPING TO BE RESURFACED AND RESET. NEW BROWNSTONE COPING TO BE FURNISHED AND INSTALLED WHERE NECESSARY.

DASH LINE INDICATED ON COPING REPRESENTS PROPOSED NEW W.I. FENCE.

PRESENT FLAGSTONE WALKS ON MAIN ST,
STATE ST, AND CENTRAL ROW, TO BE RE-

MOVED AND NEW 6" CONCRETE WALK
INSTALLED. USE 1-2-4 CONCRETE, 5'

THICK AND 1" TOP DRESSING OF 1-2 CEM. WITH METALLIC HARDENER IN SAME.

REINFORCING TO BE $\frac{1}{2}$ " ϕ DEFORMED
BARS PLACED 18" O.C. BOTH WAYS.

FULL JOINTS $\pm$ 30' APART WITH $\frac{1}{2}$ " CAREY
ELASTITE. ALL OTHER JOINTS IN TOP

LEADING: ALL OTHER JOINTS IN TOP ONLY & ARE DUMMY JOINTS.

$\frac{3}{4}$ SCALE DETAIL OF 1" x 2"
POST & RAIL CONNECTION

FULL SIZE DETAIL OF
PICKETS & TOP & BOTTOM
DOUBLE RAILS

1/2" SCALE SECTION
OF TYPICAL

BROWNSTONE COPING

1½" SCALE DETAIL OF W. I. FENCE

POSTS SET WITH MOLTEN
CAULKING LEAD