

BASEMENT PLAN HEATING & VENTILATING

MAIN FAN SCHEDULE

BASED ON CLARAGE TYPE NH CLASS-1 ARR-1- V BELT DRIVE - BELT GUARDS
VARIABLE SPEED PULLEYS ON MOTORS - SLEEVE BEARINGS - VIBRATION ELIMINATORS
WHERE CALLED FOR - VORTEX DAMPERS ON ALL INLETS - MAGNETIC CONTACTORS
FOR ALL FAN MOTORS - ALL MOTORS 3 Ø 60 CYCLE - 208 VOLT.

MARK	ZONES SERVED	CAT. NO.	CFM	S.P.	RPM	OUTLET VEL.	ROTATION	DIS.	MOTOR		
									SPEED	HP	RPM
SF#1	A-B-C	40	3000	1"	930	1300	CR	TAUD	1	3/4	1140
SF#2	K-D-P-L-S M-E-N	73	11000	1"	530	1425	CCW	UBD	1	3	1140
SF#3	X	44 1/2	4000	1"	860	1420	CR	UBD	1	1	1140
SF#4	W	44 1/2	4000	1"	860	1420	CR	UBD	1	1	1140
SF#5	Q-F-V-T R-G	60	7200	1"	631	1310	CR	UBD	1	2	1140
RF#1	A-B-C	40	3000	1"	810	1300	CR	UBD	1	3/4	1140
RF#2	K-D-P-L-S M-E-N	73	11000	1"	427	1425	CR	UBD	1	2	1140
RF#3	X	44 1/2	4000	1"	725	1420	CR	UBD	1	3/8	1140
RF#4											
RF#5	Q-F-V-T R-G	60	7200	1"	530	1310	CCW	TAUD	1	1 1/2	1140

[illegible]

SCALE: $\frac{1}{8}'' = 1' - 0''$

SCHUTZ & GOODWIN ARCHITECTS 12 HAYNES STREET HARTFORD, CONN.	
JOB NO. 53-1A	DATE <i>6/15/55</i>
SHEET NO. 42	DRAWN BY <i>V.Z.</i> TRACED BY <i>A.H.G.</i> CHECKED BY <i>V.Z.</i>
BUILDING FOR THE HARTFORD PUBLIC LIBRARY CITY OF HARTFORD - OWNER	

HENRI B. VAN ZELM AND ASSOCIATES
CONSULTING ENGINEERS
197 ASYLUM STREET
HARTFORD, CONNECTICUT