

APPROX. BEGIN OF CONSTRUCTION
STA. 12+45.60 GOODRICH STREET CL

EXCAVATE EXISTING PAVEMENT 12" BELOW FINISHED GRADE, CONSTRUCT 6" PROCESSED TRAPROCK SUBBASE, 2 1/2" PREMIXED BIT. CONC. BASE, AND 1 1/2" BIT. CONC. SURFACE COURSE (CLASS II) STA. 12+45.6 TO STA. 16+00

ALTERNATE BID ITEM: 6" RECONSTITUTED BASE, EXCAVATE AS REQUIRED FOR FINISHED GRADE, 3 1/2" PREMIXED BIT. CONC. BASE, AND 1 1/2" BIT. CONC. SURFACE COURSE (CLASS II) STA. 12+45.6 TO STA. 16+00

INSTALL GEOTEXTILE FABRIC FROM STA. 12+45.6 TO STA. 16+00 PRIOR TO PLACING SUBBASE.

INSTALL 6" BIT. CONC. LIP CURBING FROM STA. 12+64.5 TO STA. 16+00 (EXCEPT DRIVEWAYS AND CATCH BASINS)

REMOVE EXIST. CONC. CURB AND GUTTER FROM STA. 12+64.5 TO STA. 16+00

REMOVE BIT. CONC. (INCLUDE IN COST OF ROADWAY EXCAV.) INSTALL TOPSOIL & SEED.

CONSTRUCT NEW 8" REINF. CONC. SIDEWALK RAMP (TYPE 2), 5" CONC. WALK AND INSTALL NEW 6" X 20" RADIUS GRANITE CURB

INSTALL STOP BAR (12" WHITE PREFORMED PLASTIC PAVEMENT MARKINGS)

CONSTRUCT NEW 8" REINF. CONC. SIDEWALK RAMP (TYPE 1), 5" CONC. WALK AND INSTALL NEW 6" X 20" STRAIGHT GRANITE CURB

NOTES:

- INSTALL 6' OF 6" X 20" GRANITE CURB ON EACH SIDE OF CATCH BASIN WHERE INSTALLING BITUMINOUS CONCRETE LIP CURBING
- CONSTRUCT BITUMINOUS CONCRETE DRIVEWAY RAMP
- CONSTRUCT 8" REINFORCED CONCRETE DRIVEWAY RAMP
- EXISTING DRIVEWAY RAMP TO REMAIN

CALL BEFORE YOU DIG - THE CONTRACTOR IS HEREBY REMINDED THAT TITLE 16 CHAPTER 293 OF THE CONNECTICUT GENERAL STATUTES REQUIRES NOTIFICATION TO UTILITY COMPANIES OF PENDING EXCAVATION AT OR NEAR PUBLIC UTILITIES. THE CONTRACTOR SHALL CALL 1-800-922-4455 AT LEAST 48 HOURS PRIOR TO EXCAVATION.

CONSTRUCT 8" REINF. CONC. SIDEWALK

NOTE:

TOP OF CURB SHALL FOLLOW 6" ABOVE GUTTER GRADE (TYP.)

GOODRICH

STREET

PLAN

PROFILE

APPROX. BEGIN OF CONSTRUCTION
STA. 12+45.60 GOODRICH STREET CL

NOTE: CHECK GRAPHIC SCALES BEFORE USING DRAWINGS

SUPV. *ARW*
DESIGN *MDH / AEC*
DRAWN *JRM*

GRAPHIC SCALES
HORIZ. 1" = 20'
VERT. 1" = 2'

ROADWAY RECONSTRUCTION
HARTFORD, CONNECTICUT



Hayden | Wegman
Consulting Engineers

WEST HARTFORD
NEW YORK • BOSTON • BUFFALO
ATLANTA • MEMPHIS

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

DRAWN
CHECKED
SCALE
DAYBOOK NO. 010947
DATE

GOODRICH STREET

STA. 12+45.60 TO STA. 16+00

PLAN AND PROFILE

Contract No. E85-28

Job No. 845304

SHEET
1-5

CHECKED *VAC*
DATE *8.3.85*

REVISIONS
NO. DATE DESCRIPTION