

APPROX. LIMIT OF CONSTRUCTION
STA. 33+10 WESTON STREET

BM
RRS SET AT BASE OF SNET CO
POLE NO. 7344 W. SIDE OF WESTON STREET

SEE SHEET 4-5
STA. 31+50
MATCH LINE

INSTALL NEW 6"x20" STRAIGHT
GRANITE CURB FROM STA. 31+50
TO STA. 32+62.87

19" EXCAVATION TO BE PAID
UNDER ITEM NO. 34:
"EXCAVATE 17" BELOW
FINISHED GRADE"

EXCAVATE EXISTING PAVEMENT 19" BELOW FINISHED
GRADE, CONSTRUCT 12" PROCESSED TRAPROCK SUBBASE,
4" PREMIXED BIT. CONC. BASE, AND 3" BIT. CONC. SURFACE
(CLASS I, TWO COURSES) STA. 31+50 TO STA. 33+10

ALTERNATE BID ITEM: 8" RECONSTITUTED BASE, EXCAVATE
AS REQUIRED FOR FINISHED GRADE, 4" PREMIXED BIT
CONC. BASE, AND 3" BIT. CONC. SURFACE (CLASS I, TWO
COURSES) STA. 31+50 TO STA. 33+10

INSTALL 6" BIT. CONC. LIP CURBING
FROM STA. 32+62.87 TO STA. 33+10

INSTALL HARTFORD TYPE "C" CATCH-BASIN
INV. = 17.00

INSTALL 27' OF NEW 12" PVC DRAIN PIPE, S = 4.52%

INSTALL HARTFORD TYPE "C" CATCH-BASIN, INV. = 15.78

INSTALL 16.5' OF NEW 12" PVC DRAIN PIPE, S = 4.52%

INSTALL 3' W X 4' X 1' DEEP MODIFIED RIPRAP ON
6" PROCESSED TRAPROCK

INV. = 15.04

BM
N. BOLT OF HYDRANT
ELEV. = 24.25

WESTON

STREET

PLAN

NOTE:
TOP OF CURB SHALL FOLLOW 6" ABOVE GUTTER GRADE (TYP.)

APPROX. LIMIT OF CONSTRUCTION
STA. 33+10 WESTON STREET

PROFILE

NOTE: CHECK GRAPHIC SCALES BEFORE USING DRAWINGS

NO.	DATE	DESCRIPTION
1	7-2-85	REVISIONS

SUPV.	ARW
DESIGN	DA/AC
DRAWN	EPF
CHECKED	JAC
DATE	7-2-85

GRAPHIC SCALES
HORIZ. 1" = 20'
VERT. 1" = 2'

ROADWAY RECONSTRUCTION
HARTFORD, CONNECTICUT



Hayden | Wegman
Consulting Engineers

WEST HARTFORD
NEW YORK • BOSTON • BUFFALO
ATLANTA • MEMPHIS

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

WESTON STREET
STA. 31+50 TO STA. 33+10

DRAWN
CHECKED
SCALE
DATE
DAYBOOK NO. 010947

PLAN AND PROFILE
Contract NO. E85-28
Job No. 845304

SHEET
5
OF
5