

APPROX. BEGIN OF
CONSTRUCTION

STA. 10+41
WOODSTOCK
STREET
N 163562.3141
E 162935.9792

15 CONSTRUCT NEW 8" REIN. CONC. SIDEWALK RAMP (TYPE 1),
5" CONC. WALK AND INSTALL 21LF OF NEW 6"x20" STRAIGHT
GRANITE CURB

WC= WROUGHT IRON CEMENT
LINED WATER PIPE

INSTALL STOP BAR
(12" WHITE PREFORMED PLASTIC PAVEMENT MARKINGS)

EXISTING SIDEWALK RAMP, CONC. WALK
AND RADIUS GRANITE CURB TO REMAIN

INSTALL GEOTEXTILE FABRIC
STA. 10+41 TO STA. 13+50
PRIOR TO PLACING SUBBASE

EXCAVATE EXISTING PAVEMENT 12" BELOW FINISHED
GRADE, CONSTRUCT 8" PROCESSED TRAPROCK SUBBASE,
2 1/2" PREMIXED BIT. CONC. BASE, AND 1 1/2" BIT. CONC.
SURFACE COURSE (CLASS 1) STA. 10+41 TO STA. 13+50

INSTALL 6" BIT. CONC. LIP CURBING
FROM STA. 10+64 TO STA. 13+50.
(EXCEPT DRIVEWAYS AND CATCH BASINS)

REMOVE EXISTING CONC. CURB AND GUTTER
FROM STA. 10+64 TO STA. 13+50

REMOVE EXISTING STRAIGHT GRANITE CURB
(69'±) TO BE INCLUDED IN COST OF ROADWAY EXCAVATION
N. STREET LINE

WOODSTOCK

STREET

R=15'
L=18.98'
Δ=72°-30'-27.63"
T=11'

3 INSTALL 6" BIT. CONC. LIP CURBING
FROM STA. 10+46 TO STA. 13+50
(EXCEPT DRIVEWAYS AND CATCH BASINS)

REMOVE EXISTING CONC. CURB AND GUTTER
FROM STA. 10+46 TO STA. 13+50

35 CONSTRUCT NEW 8" REIN. CONC. SIDEWALK RAMP (TYPE 2),
5" CONC. WALK AND INSTALL NEW 6"x20" RADIUS GRANITE CURB

34 CALL BEFORE YOU DIG - THE CONTRACTOR IS HEREBY
REMINDED THAT TITLE 16 CHAPTER 293 OF THE CONNECTICUT
GENERAL STATUTES REQUIRES NOTIFICATION TO UTILITY
COMPANIES OF PENDING EXCAVATION AT OR NEAR PUBLIC
UTILITIES. THE CONTRACTOR SHALL CALL 1-800-922-4455
AT LEAST 48 HOURS PRIOR TO EXCAVATION.

NOTES:

19 INSTALL 6' OF 6"x20" GRANITE CURB ON EACH SIDE OF
CATCH BASIN WHERE INSTALLING BITUMINOUS CONCRETE LIP CURBING

31 (B) CONSTRUCT BITUMINOUS CONCRETE DRIVEWAY RAMP

32 (C) CONSTRUCT 8" REINFORCED CONCRETE DRIVEWAY RAMP

33 (E) EXISTING DRIVEWAY RAMP TO REMAIN

PLAN

APPROX. BEGIN OF
CONSTRUCTION
STA. 10+41
WOODSTOCK
STREET

21 PROPOSED TOP OF CURB
22 PROPOSED GUTTER

GRADE TO MATCH EXISTING

GRADE TO MATCH EXISTING

GRADE TO MATCH EXISTING

PROPOSED

155 N

155 S

155 H

155 H

155 H

155 H

155 H

155 H

155 H

155 H

155 H

155 H

155 H

PROFILE

NOTE:
TOP OF CURB SHALL FOLLOW 6"
ABOVE GUTTER GRADE (TYP)

EXISTING BACK OF WALK
EXISTING FRONT OF WALK
EXISTING CURB
EXISTING GUTTER

EXISTING

EXISTING

EXISTING

EXISTING

EXISTING

EXISTING

EXISTING

NOTE: CHECK GRAPHIC SCALES BEFORE USING DRAWINGS

SUPV. ARW		GRAPHIC SCALES		ROADWAY RECONSTRUCTION HARTFORD, CONNECTICUT		Hayden Wegman Consulting Engineers		CITY OF HARTFORD, CONNECTICUT DEPARTMENT OF PUBLIC WORKS BUREAU OF ENGINEERING SERVICES		WOODSTOCK STREET STA. 10+41 TO STA. 13+50		SHEET 1	
DESIGN AC/DH		HORIZ. 1"=20'				WEST HARTFORD		SCALE DAYBOOK N0010956		PLAN AND PROFILE		OF 3	
DRAWN EPF		VERT. 1"=2'				NEW YORK • BOSTON • BUFFALO		DATE		Contract E85-34		Job No.- 845304	
CHECKED JAC						ATLANTA • MEMPHIS							
DATE 6-25-85													