

NOTES:
1. INSTALL 6" OF 6"x20" GRANITE CURB ON EACH SIDE OF CATCH BASIN WHERE INSTALLING BITUMINOUS CONCRETE LIP CURBING
2. CONSTRUCT BITUMINOUS CONCRETE DRIVEWAY RAMP
3. CONSTRUCT 8" REINFORCED CONCRETE DRIVEWAY RAMP
4. EXISTING DRIVEWAY RAMP TO REMAIN
5. CALL BEFORE YOU DIG - THE CONTRACTOR IS HEREBY REMINDED THAT TITLE 16 CHAPTER 293 OF THE CONNECTICUT GENERAL STATUTES REQUIRES NOTIFICATION TO UTILITY COMPANIES OF PENDING EXCAVATION AT OR NEAR PUBLIC UTILITIES. THE CONTRACTOR SHALL CALL 1-800-922-4455 AT LEAST 48 HOURS PRIOR TO EXCAVATION.

N163300

N163200

APPROX. LIMIT OF CONSTRUCTION
STA. 10+52.5 BRANFORD STREET C

EXCAVATE EXISTING PAVEMENT 12" BELOW FINISHED GRADE, CONSTRUCT 8" PROCESSED TRAPROCK SUBBASE, 2 1/2" PREMIXED BIT. CONC. BASE, AND 1 1/2" BIT. CONC. SURFACE COURSE (CLASS 1) STA. 10+52.5 TO STA. 14+50

INSTALL GEOTEXTILE FABRIC PRIOR TO PLACING SUBBASE STA. 10+52.5 TO STA. 14+50

INSTALL STOP BAR (12" WHITE PREFORMED PLASTIC PAVEMENT MARKINGS)

INSTALL 6" BIT. CONC. LIP CURBING FROM STA. 10+78 TO STA. 14+50 (EXCEPT DRIVEWAYS AND CATCH BASINS)

REMOVE EXISTING CONC. CURB AND GUTTER FROM STA. 10+78 TO STA. 14+50

CONSTRUCT NEW 8" REINF. CONC. SIDEWALK RAMP (TYPE 2) 5" CONC. WALK AND RESET RADIUS GRANITE CURB

REMOVE EXISTING CONC. CURB AND GUTTER FROM STA. 10+58 TO STA. 14+50

INSTALL 6" BIT. CONC. LIP CURBING FROM STA. 10+58 TO STA. 14+50 (EXCEPT DRIVEWAYS AND CATCH BASINS)

CONSTRUCT NEW 8" REINF. CONC. SIDEWALK RAMP (TYPE 2) 5" CONC. WALK AND INSTALL NEW 6"x20" RADIUS GRANITE CURB

RR SPIKE AT BASE S.N.E.T.C.O. NO. 6187 ELEV. = 166.29

REMOVE EXISTING BIT CONC. (TO BE INCLUDED IN COST OF ROADWAY EXCAVATION) TOPSOIL AND SEED

RR SPIKE AT BASE OF S.N.E.T.C.O. NO. 6189 ELEV. = 179.16

WC = WROUGHT IRON CEMENT LINED WATER PIPE

PLAN

APPROX. LIMIT OF CONSTRUCTION
STA. 10+52.5 BRANFORD STREET C

PROFILE

SUPV. ARW	
DESIGN AC/DM	
DRAWN KHT	
CHECKED JAC	
DATE 6-25-85	
REVISIONS	
NO.	DATE DESCRIPTION
1	6/29/86 As-Built in Profile (Elevations) (A.J.S.)

GRAPHIC SCALES
HORIZ. 1" = 20'
VERT. 1" = 2'

ROADWAY RECONSTRUCTION
HARTFORD, CONNECTICUT



Hayden | Wegman
Consulting Engineers

WEST HARTFORD
NEW YORK • BOSTON • BUFFALO
ATLANTA • MEMPHIS

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

DRAWN _____
CHECKED _____
SCALE _____
DAYBOOK NO. Q10956
DATE _____

BRANFORD STREET
STA. 10+52.5 TO STA. 14+50

PLAN AND PROFILE

Contract #E85-34 Job No. 845304 OF 3