

CURB REMOVAL

LEFT OR WEST SIDE			RIGHT OR EAST SIDE		
TYPE OF CURB	FROM STATION	TO STATION	TYPE OF CURB	FROM STATION	TO STATION
GRANITE	13+83.4	14+23.8	CONCRETE	12+94.5	14+04.7
CONCRETE	14+23.8	14+51.9	GRANITE	14+04.7	14+30.0
GRANITE	14+51.9	14+73.8	CONCRETE	14+30.0	14+64.9
CONCRETE	14+73.8	15+29.6	GRANITE	14+64.9	14+80.4
GRANITE	15+29.6	15+84.3	CONCRETE	14+80.4	15+55.0
CONCRETE	15+84.3	16+25.2	GRANITE	15+55.0	15+68.3
GRANITE	16+25.2	16+62.4	CONCRETE	15+68.3	18+00.3
CONCRETE	16+62.4	16+75.2			
GRANITE	16+75.2	16+91.4			
CONCRETE	16+91.4	18+00.3			

NOTES:

RIM OR FRAME ELEVATIONS OF ALL UTILITY GATE BOXES, HANDHOLES, AND CATCH BASINS ARE TO BE ADJUSTED AS REQUIRED TO MATCH PROPOSED FINISHED PAVED SURFACES.

(B) CONSTRUCT BIT. CONC. DRIVEWAY RAMP

(C) SAWCUT BETWEEN EXISTING RAMPED SECTION AND SIDEWALK AND CONSTRUCT 8" REINF. CONC. DRIVEWAY RAMP

(E) EXIST. DRIVEWAY RAMP TO REMAIN

(S) CONSTRUCT 8" REINF. CONC. SIDEWALK

CALL BEFORE YOU DIG - THE CONTRACTOR IS HEREBY REMINDED THAT TITLE 16 CHAPTER 293 OF THE CONNECTICUT GENERAL STATUTES REQUIRES NOTIFICATION TO UTILITY COMPANIES OF PENDING EXCAVATION AT OR NEAR PUBLIC UTILITIES. THE CONTRACTOR SHALL CALL 1-800-922-4455 AT LEAST 48 HOURS PRIOR TO EXCAVATION.

MATCH LINE STA. 14+00 SEE SHT. 16 OF 41

MATCH LINE STA. 14+00 SEE SHT. 16 OF 41

14+00 GIDDINGS-PP2/2

NOTE: CHECK GRAPHIC SCALES BEFORE USING DRAWINGS

GRAPHIC SCALES

HORIZ. 1"=20'

VERT. 1"=2'

ROADWAY RECONSTRUCTION
HARTFORD, CONNECTICUTHayden | Wegman
Consulting EngineersWEST HARTFORD
NEW YORK • BOSTON • BUFFALO
ATLANTA • MEMPHISCITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

DAYBOOK NO. 011005

DATE

GIDDINGS STREET
STA. 14+00 TO STA. 18+00.33

PLAN AND PROFILE

Contract No. E86-2 Job No. - 852534

SHEET 17

OF 41

PLAN

NOTE:
TOP OF PROP CURB SHALL FOLLOW 6" ABOVE GUTTER GRADE (TYP)

PROFILE

APPROX. LIMIT OF CONSTRUCTION
STA. 18+00.33 GIDDINGS STREETAPPROX. LIMIT OF CONSTRUCTION
STA. 18+00.33 GIDDINGS ST.BM
NAIL IN HELCO POLE NO. 4292
EL. 59.667BM
NE CORNER TOP CONC. STOOP AT
HOUSE #61, GIDDINGS ST.
EL. 62.517BM
CMS SW. CORNER GIDDINGS
AND DEXTER
EL. 61.22CMS-2
N 140165.3640
E 158789.9078PC STA. 18+00.33
EL. 60.79 6PC STA. 18+00.33
EL. 60.85 617" EXCAVATION, 12" TRAPROCK BASE, 3/4" PREP. 1 1/2" SURFACE
STRIP EXIST. BIT. CONC., CONSTRUCT 2" PREP. CONC. BINDER COURSE AND 2" BIT. CONC. SURFACE COURSE (CLASS 1) STA. 14+00 TO STA. 18+00.33
INSTALL GEOTEXTILE FABRIC, ETC.INSTALL 6" B.C.L.C. FROM STA. 14+00
TO STA. 18+00.33 (EXCEPT DRIVEWAYS)
CONSTRUCT 5" CONC. SIDEWALK
STA. 15+19 TO STA. 16+00
(EXCEPT REINF. CONC. SIDEWALK)INSTALL STOP BAR
(12" WHITE PREFORMED PLASTIC PAVEMENT MARKINGS)REMOVE EXISTING CURBING
SEE TABLE ABOVE

GIDDING

STREET

DEXTER

MATCH LINE STA. 14+00 SEE SHT. 16 OF 41

MATCH LINE STA. 14+00 SEE SHT. 16 OF 41

14+00 GIDDINGS-PP2/2

NOTE: CHECK GRAPHIC SCALES BEFORE USING DRAWINGS

GRAPHIC SCALES

HORIZ. 1"=20'

VERT. 1"=2'

ROADWAY RECONSTRUCTION
HARTFORD, CONNECTICUTHayden | Wegman
Consulting EngineersWEST HARTFORD
NEW YORK • BOSTON • BUFFALO
ATLANTA • MEMPHISCITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

DAYBOOK NO. 011005

DATE

GIDDINGS STREET
STA. 14+00 TO STA. 18+00.33

PLAN AND PROFILE

Contract No. E86-2 Job No. - 852534

SHEET 17

OF 41