



ALONG MAIN STREET THE FOLLOWING WORK TO BE PERFORMED
ON EXISTING WROUGHT IRON FENCE AND GATES.

- A - IN MAIN ENTRANCE REPAIR ONE HALF OF GATE AND INSTALL
OTHER HALF THAT IS MISSING.
- B - COUNTING NORTHERLY FROM MAIN ENTRANCE REPAIR FENCE
SECTIONS, 4 - 13 - 15 - 25 - 26 - 29 - 37 - 38 - 40 AND REPAIR
GATE BETWEEN SECTIONS 39 AND 40.
- C - COUNTING SOUTHERLY FROM MAIN ENTRANCE REPAIR FENCE
SECTIONS, 13 - 15 - 16 - 17 - 28 - 30 - 33. SECTION 33 IS
LOCATED ON MATHER STREET. AND INSTALL NEW SECTION
27 WITH BOLL BOLTS, NUTS, AND ANGLE BRACKETS
REPLACE ALL BOLTS, NUTS, AND ANGLE BRACKETS
OF SECTIONS 15 - 16 - 17

THERE ARE 8 SETS OF BOLTS AND NUTS AND ANGLE BRACKETS SUPPORTING EACH SECTION TO FENCE POSTS.

CITY PARKS AND RECREATION DEPARTMENT WILL FURNISH THE MISSING FENCE AND GATE MATERIALS EXCEPT NEW SECTION 27.

<h1 style="margin: 0;">CITY OF HARTFORD, CONNECTICUT</h1> <h2 style="margin: 0;">DEPARTMENT OF PUBLIC WORKS</h2> <h3 style="margin: 0;">BUREAU OF ENGINEERING SERVICES</h3>		
<h1 style="margin: 0;">OLD NORTH CEMETERY FENCE IMPROVEMENTS</h1>		
SUBMITTED <i>Rama Rao Avala</i> PROJECT ENGINEER	RECOMMENDED <i>[Signature]</i> DIVISION MANAGER	APPROVED <i>[Signature]</i> CITY ENGINEER, ESB
DRAWN <u>W.J.P.</u> CHECKED <u>R.A.</u>	SCALE 1" = 50'	DAYBOOK NO. 011151 DATE SEPTEMBER 1988