



1. ELEVATIONS ARE BASED ON METROPOLITAN DISTRICT COMMISSION DATUM.
2. RIM OR FRAME ELEVATIONS OF ALL UTILITY STRUCTURES OR CATCH BASINS ARE TO BE ADJUSTED AS REQUIRED TO MEET FINISHED GRADE.
3. CATCH BASINS DAMAGED OR FILLED WITH SEDIMENTATION DURING CONST. WILL BE CLEANED AND FLUSHED AT THE CONTRACTORS EXPENSE.
4. CALL BEFORE YOU DIG- THE CONTRACTOR IS HEREBY REMINDED THAT "PUBLIC ACT NO. 87-71" OF THE CT. GENERAL STATUTES REQUIRES NOTIFICATION TO UTILITY COMPANIES OF PENDING EXCAVATION AT OR NEAR THE LOCATION OF PUBLIC UTILITY FACILITIES. THE CONTRACTOR SHALL CALL 1-800-922-4455 AT LEAST 48 HRS. PRIOR TO EXCAVATION.
5. STREET LAYOUTS ARE BASED UPON RECORDED DATA BY THE CITY OF HARTFORD.
6. ALL PLASTIC PAVEMENT MARKINGS ARE TO BE INSTALLED DURING FINAL ROUTING OPERATIONS AND BE "INLaid" WITHIN THE BIT. CONC. SURFACE COARSE.
7. BENCHMARK ELEVATIONS ARE AS NOTED ON PLAN.
8. DEPRESS ALL CURBING AT SIDEWALK RAMPS AS DETAILED OR DIRECTED BY THE ENGINEER.
9. LINE AND GRADE WILL BE PROVIDED BY THE CITY OF HARTFORD, THE CONTRACTOR IS REQUIRED TO REQUEST LAYOUT AT LEAST 48 HRS. IN ADVANCE.
10. THE CONTRACTOR IS REQUIRED TO OBTAIN ALL REQUIRED PERMITS PRIOR TO BEGINNING WORK.
11. STATIONS MEASURED ALONG NORTH CURB AND ON GRADE.
12. THE CONTRACTOR SHALL UTILIZE STEEL PLATES TO PROTECT NEWLY CONSTRUCTED CONCRETE ROAD BASE FOR A MINIMUM OF 24HRS.

SHEET 6 OF 6

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
ENGINEERING SERVICES BUREAU

RECONSTRUCTION
OF
ASHLEY STREET

SUBMITTED <i>AD 12/2/91</i>	RECOMMENDED <i>Jan 7 1992</i>	APPROVED <i>Anthony J. Howard</i>
PROJECT ENGINEER	DIVISION ENGINEER	CITY ENGINEER
DRAWN <i>J.L.B.</i>	SCALE	DAYBOOK NO. 011232B
CHECKED _____	1" = 20'-0" HOR. 1" = 2'-0" VERT.	DATE JANUARY 1991
		FILE NAME ASHLEY1.DWG

