

FIRE STATION NO. 2 ROOM FINISH SCHEDULE						
ROOM NO.	ROOM NAME	FLOOR	BASE	WALL	CEILING	COMMENT
F1	OFFICE	VT	—	—	NOTE 1	NOTE 3,8
F2	STORAGE	—	—	—	—	
F3	KITCHEN	VT	—	—	NOTE 1	NOTE 8
F4	TURN-OUT	NOTE 4	—	—	—	NOTE 14
F5	STORAGE	—	—	—	—	
F6	CELLAR STAIR	—	—	—	—	
F7	DAY ROOM	VT	—	—	NOTE 1	NOTE 8
F8	TOILET	VT	—	—	—	NOTE 8
F9	CAPTAIN RM.	VT	—	—	NOTE 1	NOTE 8
F10	APPARATUS	—	—	—	NOTE 2	NOTE 8
F11	TOILET	VT	—	—	—	NOTE 8
F12	WATCH RM.	VT	VT	—	NOTE 1	NOTE 8
F13	ALCOVE	VT	—	—	—	NOTE 8
STAIR F1	STAIR NO.1	VT	PAINT (WOOD)	PAINT (VITRO)	PAINT	NOTE 5, 7, 20, 16
STAIR F2	STAIR NO.2	VT	PAINT (WOOD)	PAINT (VITRO)	PAINT	NOTE 5, 7, 20, 16
F12A	PHONE BOOTH	VT	—	—	—	
F9A	CLOSET	VT	—	—	—	
S1	DORMITORY	VT	VT	PAINT	PAINT	NOTE 8, 6
S2	DORMITORY	VT	VT	PAINT	PAINT	NOTE 8, 6, 15
S3	DORMITORY	VT	VT	PAINT	PAINT	NOTE 8, 6,
S4	OFFICER RM.	VT	VT	PAINT	PAINT	NOTE 8, 6
S4A	CLOSET	VT	VT	PAINT	PAINT	NOTE 9, 6
S5	TOILET	VT	VT	PAINT	PAINT	NOTE 6, 8
S6	TOILET	VT	VT	PAINT	PAINT	NOTE 6, 8
S7	OFFICER RM.	VT	VT	PAINT	PAINT	NOTE 8, 6
S7A	CLOSET	VT	VT	PAINT	PAINT	NOTE 9, 6
S8	STAIR HALL	VT	VT	PAINT	NOTE 1	NOTE 6
S9	LOCKER RM.	VT	VT	PAINT	PAINT	NOTE 6, 8, 21, 22
S10	CLOSET	—	—	—	—	
S11, S12	FINISHES NOT IN CONTRACT	—	—	—	—	SEE PLAN FOR NEW LIGHT FIXTURES
S13	OFFICER RM.	VT	VT	PAINT	PAINT	NOTE 8, 6
S13A	CLOSET	VT	VT	PAINT	PAINT	NOTE 9, 6
S14	CLOSET	VT	VT	PAINT	PAINT	NOTE 9, 6
S15	TOILET	VT	VT	PAINT	PAINT	NOTE 6, 8
S16 - S20	FINISHES NOT IN CONTRACT	—	—	—	—	SEE PLAN FOR NEW LIGHT FIXTURES
S21	HALL	VT	VT	PAINT	PAINT	NOTE 6
S22	SHOWER	—	—	PAINT (NOTE 13)	PAINT	NOTE 6, 8, 19,
S23	HALL	NOTE 11	—	PAINT	PAINT	NOTE 6
S24	WASH	—	—	PAINT (NOTE 13)	PAINT	NOTE 6, 8, 19
S25	HALL	NOTE 11	—	PAINT	PAINT	NOTE 6
S26	TOILET	—	NOTE 13	PAINT (NOTE 12)	PAINT	NOTE 6
S27	HALL	VT	VT	PAINT	PAINT	NOTE 6
S28	LOCKER RM.	VT	VT	PAINT	PAINT	NOTE 6, 8, 21, 22
S29-S33	FINISHES NOT IN CONTRACT	—	—	—	—	SEE PLAN FOR NEW LIGHT FIXTURES
S34	OFFICER RM.	VT	VT	PAINT	PAINT	NOTE 6, 8
S35	CLOSET	VT	VT	PAINT	PAINT	NOTE 6, 9
S36	TOILET	VT	VT	PAINT	PAINT	NOTE 6, 8
S37	STAIR HALL	VT	VT	PAINT	NOTE 1	NOTE 6
S38	FUNCTION RM.	VT	VT	—	NOTE 1	NOTE 10, 15
STAIR S1	STAIR NO.1	VT	PAINT (WOOD)	PAINT (VITRO)	PAINT	NOTE 6, 7, 20, 16
STAIR S2	STAIR NO.2	VT	PAINT (WOOD)	PAINT (VITRO)	PAINT	NOTE 6, 7, 20, 16
NOTE	VT = VINYL TILE					

ROOM FINISH SCHEDULE NOTES

- EXISTING SUSPENDED CEILING GRID TO REMAIN. REMOVE EXISTING ACOUSTIC PANELS AND LIGHT FIXTURES. CHECK ALL SUSPENSION HANGERS FOR SUITABILITY. PAINT EXPOSED SURFACES OF GRID. PROVIDE NEW ACOUSTIC PANELS. PROVIDE NEW LIGHT FIXTURES (SEE ELEC. SPEC.)
- RMLF-10 : SEE NOTE ON PLAN TO PATCH WOOD CEILING.
- RM. F-1 : PROVIDE PAINTED WOOD PATCH AT WINDOW BENCH.
- RM. F-4 : SEE PLAN NOTE TO PATCH WOOD FLOOR.
- STAIRS NO.1,2 : SEE PLAN NOTE TO REPAIR WOOD BALUSTRADE.
- PLASTER WALLS AND PLASTER CEILINGS : WHERE SCHEDULED FOR PAINTING, REPAIR CRACKS AND HOLES (SOME PROMINENT HOLES ARE LOCATED ON DRAWING). REFINISH ALL WOOD DOORS & TRIM AS PER EXISTING FINISH MATERIALS.
- STAIRS NO.1,2 : REFINISH WOOD TRIM, BALUSTRADES, RAILINGS.
- EXISTING METAL RADIATORS, BASEBOARD HEATING, CONVECTORS TO BE PAINTED. AT ABOUT (4) EXISTING RADIATORS, PAINT BACKUP WALL TO MATCH EXISTING WALL FINISH. (PROVIDE LABOR FOR MOVING RADIATORS).
- CLOSETS : PAINT WOOD SHELF & POLE.
- RM. S-38/POLE WELLS : PAINT WALLS & CEILINGS. REFINISH DOORS & TRIM.
- RMS. S-23,25 : REPAIR HOLE AT CERAMIC TILE FLOOR.
- RM. S-26 : NORTH (URINAL WALL) WALL TO RECEIVE "VITROCKEM" PAINT.
- RMS. S-22,24 : CERAMIC WAINSCOT NOT IN CONTRACT.
- RM. F-4 : PAINT RE-HUNG DOOR & TRIM. (SEE PLAN NOTE).
- RMS. S-2,38 : SEE PLAN NOTE FOR DEMOLITION AND PATCHING.
- STAIRS : VT TILE TREADS, VT NOSINGS, PAINTED RISERS, PAINTED BALUSTRADE AND WOOD TRIM. VT TILE LANDINGS.
- PROVIDE VINYL BASE TO MATCH EXISTING, WHERE BASE IS MISSING.
- RMS. S-22,24 : PAINT METAL DUCT WORK AT CEILINGS.
- STAIR NO.1,2 : WHERE NOTED "VITRO", PROVIDE EPOXY PAINT, AT PLASTER WALLS, TO A STRAIGHT LINE MEASURING 6'-0" ABOVE STAIR NOSINGS AND AROUND LANDINGS. PROVIDE OTHER SPECIFIED PAINT AT PLASTER WALLS ABOVE. (CONTRACTOR'S OPTION : PAINT EPOXY PAINT FULL HEIGHT.)
- RMS. S-9,28 : MOVE METAL LOCKERS AS REQUIRED TO PROVIDE NEW FINISHES.
- RMS. S-9,28 : REFINISH BENCHES (WOOD SEAT, METAL STANDS).

CITY OF HARTFORD, CONNECTICUT  
DEPARTMENT OF PUBLIC WORKS

FIRE STATION RENOVATIONS  
HARTFORD CONNECTICUT

FIRE STATION NO. 2

SUBMITTED <i>F. M. Delaney</i>	APPROVED <i>Frank Verano</i>	APPROVED <i>Anthony P. ...</i>
DESIGNED FJM	SCALE	CITY ENGINEER
DRAWN FJM	DATE FEB. 28, 1991	DRAWING NO.
CHECKED FAV	DAYBOOK NO. 011208-D	4

CONTRACT NO. F9H12