

EROSION CONTROL INSTALLATION

1. INSTALL SILT FENCE AND HAY BALE DAMS AROUND THE DISTURB AREA OF THE PARK BEFORE COMMENCING ANY CONSTRUCTION. DO NOT INSTALL SILT FENCE AROUND THE PERIMETER OF TOPSOIL STOCKPILE AREA UNTIL ALL DRAINAGE WORK IS COMPLETED.
2. INSTALL HAY BALE DAMS AROUND EXISTING CATCH BASINS IMMEDIATELY.
3. DURING THE COURSE OF THE CONTRACTORS OPERATIONS, IT WILL BE NECESSARY TO TEMPORARILY REMOVE, ADJUST, OR RELOCATE SILT FENCING OR HAY BALE DAMS. IT IS THE CONTRACTORS RESPONSABILITY TO PERFORM THIS WORK ON AN AS NEEDED BASIS. THERE WILL BE NO ADDITIONAL COMPENSATION FOR REMOVING, RELOCATING, OR ADJUSTING HAY BALE DAMS OR SILT FENCING FOR THE PURPOSES OF FACILITATING CONSTRUCTION.
4. IT IS INTEND THAT THE TOPSOIL STOCKPILE AREA PROVIDE ADEQUATE AREA TO TEMPORARILY STORE MATERIAL UNTIL IT IS TOBE UTILIZED. THE CONTRACTOR MAY SUBMIT ALTERNATIVE LOCATION(S) FOR STOCKPIILING TOPSOIL HOWEVER THESE LOCATIONS ARE SUBJECT TO THE APPROVAL OF THE ENGINEER.
5. SEDIMENTATION WHICH COLLECTS AT SILT FENCING OR HAY BALE DAMS IS TO BE REMOVED IMMEDIATLY. ANY DAMAGE OR EROSION RESULTING FROM THE CONTRACTORS OPERATIONSHALL BE IMMEDIATLY RESTORED TO ORIGINAL CONDITION.

CONSTRUCT 3" BITUMINOUS CONCRETE WHEELCHAIR RAMP

INSTALL 6" X 6" TIMBER EDGE

INSTALL PLAYSCAPE STRUCTURE (ITEM 346)

CONSTRUCT CHILD SAFE AREA

SOD WITHIN PROPOSED AREA AND SEED ALL DISTURBED AREAS

SODDING AREA

LIMIT OF SODDING AREA

PLACE HAY BALES

RESPT. EXISTING C.B. AND M.H. FRAME & COVER

PLACE HAY BALES

EXISTING STORM DRAIN

EXISTING SAN. DRAIN

INSTALL SILT FENCE

SEED ALL DISTURBED AREAS

INSTALL FITNESS COURSE STRUCTURE (BID ITEM 347)

CITY OF HARTFORD, CONNECTICUT DEPARTMENT OF PUBLIC WORKS ENGINEERING SERVICES BUREAU			
PLAN FOR INSTALLATION OF PLAYGROUND AND FITNESS COURSE STRUCTURES AT McDONOUGH SCHOOL			
SUBMITTED PROJECT ENGINEER <i>M. Haslam</i>	RECOMMENDED DIVISION MANAGER <i>[Signature]</i>	APPROVED ENGINEER <i>[Signature]</i>	
DRAWN G.S. CHECKED M.B.	SCALE: HORIZ. 1" = 20' VERT. 1" = 2'	DAYBOOK NO. 011246 A DATE SEPTEMBER 1991 FILE NAME E91-33	SHEET 1 OF 1

Bernard E. Janowski 3/25/92
APPROVED: PARKS AND RECS DATE: