

EROSION CONTROL INSTALLATION

- 1. INSTALL SILT FENCE AND HAY BALE DAMS AROUND THE PERIMETER OF THE PARK BEFORE COMMENCING ANY CONSTRUCTION. DO NOT INSTALL SILT FENCE AROUND THE PERIMETER OF TOPSOIL STOCKPILE AREA UNTIL ALL DRAINAGE WORK IS COMPLETED.
- 2. INSTALL HAY BALE DAMS AROUND EXIST CATCH BASINS IMMEDIATELY. INSTALL HAY BALE DAMS AROUND NEWLY INSTALL CATCH BASINS UPON THEIR COMPLETION.
- 3. DURING THE COURSE OF THE CONTRACTORS OPERATIONS IT WILL BE NECESSARY TO TEMPORARILY REMOVE, ADJUST, OR RELOCATE SILT FENCING OR HAY BALE DAMS. IT IS THE CONTRACTORS RESPONSIBILITY TO PERFORM THIS WORK ON AN AS-NEEDED BASIS. THERE WILL BE NO ADDITIONAL COMPENSATION FOR REMOVING, RELOCATING, OR ADJUSTING HAY BALE DAMS OR SILT FENCING FOR THE PURPOSES OF FACILITATING CONSTRUCTION.
- 4. IT IS INTEND THAT THE TOPSOIL STOCKPILE AREA PROVIDE ADEQUATE AREA TO TEMPORARILY STORE MATERIAL UNTIL IT IS TO BE UTILIZED. THE CONTRACTOR MAY SUBMIT ALTERNATIVE LOCATION(S) FOR STOCKPILING TOPSOIL HOWEVER THESE LOCATIONS ARE SUBJECT TO THE APPROVAL OF THE ENGINEER.
- 5. SEDIMENTATION WHICH COLLECTS AT SILT FENCING OR HAY BALE DAMS IS TO BE REMOVED IMMEDIATELY. ANY DAMAGE OR EROSION RESULTING FROM THE CONTRACTORS OPERATIONS SHALL BE IMMEDIATELY RESTORED TO ORIGINAL CONDITION.

LAWN BOWLING COURT

TENNIS COURT

EXISTING LITTLE LEAGUE FIELD

OUTFIELD TO BE MACHINE SEED

TO TEMPORARY CONSTRUCTION ENTRANCE (FIELD LOCATED BY ENGINEER)

CITY OF HARTFORD, CONNECTICUT
DEPARTMENT OF PUBLIC WORKS
BUREAU OF ENGINEERING SERVICES

SITE LAYOUT AND INSTALLATION
PLAN FOR
ELIZABETH PARK / WEST

SUBMITTED: [Signature] RECOMMENDED: [Signature] APPROVED: [Signature]
PROJECT ENGINEER DIVISION MANAGER CITY ENGINEER, ESB

REV.	SHEET	DRAWN	SCALE	DAYBOOK
4/2/91	2 OF 4	G.S.	1"=20'	NO. 011222-A
		CHECKED		DATE
		M.K.		7/24/90

APPROVED: [Signature] DATE 7-24-90
CITY OF HARTFORD PARK AND RECREATION