

629/11



TREE CALIPER	NO. OF GUYS	NO. OF TWISTED STRANDS	WIRE	ANCHORAGE
UNDER 4"	3	2	12 GAUGE	36" STAKES (AS SHOWN)
4"-6"	3	EITHER 3 OR 2	12 GAUGE 10 GAUGE	36" STAKES (AS SHOWN)
6"-12"	4	EITHER 3 OR 2	10 GAUGE 1/2" CABLE	8" ex 48" DEADEND- 48" BELOW GRADE
12" AND OVER	4	EITHER 3 OR 2	10 GAUGE 5/8" CABLE	8" ex 48" DEADEND- 48" BELOW GRADE



629/