



- INSTALL TWO HARBALL FIELDS AND THREE SOFTBALL FIELDS
AS SHOWN ON DETAIL DRAWINGS.
INSTALL 16' HIGH CHAIN LINK FENCE FOR BALL FIELDS BACKSTOPS
AS SHOWN ON STANDARD DETAIL SHEET.
INSTALL 6' HIGH CHAIN LINK FENCE AND 20' PLAYER'S BENCHES
ON ALL BALL FIELDS.
REMOVE EXISTING BLEACHERS AND DELIVER TO PARKS AND
RECREATION DEPARTMENT REPRESENTATIVE. (PAID FOR UNDER
SITE PREPARATION ITEM.)
REMOVE ALL EXISTING BACKSTOPS AND BENCHES AND DELIVER
THEM TO CITY YARD.
REMOVE ALL CONCRETE FOOTINGS FOR BACKSTOPS, BLEACHERS
AND BENCHES TO TWO (2) FEET BELOW FINISHED GRADE.

NO.	DATE	DESCRIPTION	BY