



- DEMOLITION NOTES:**
1. THE UNDERGROUND UTILITIES SHOWN ON THIS PLAN HAVE BEEN OBTAINED FROM AVAILABLE RECORDS AND HAVE BEEN LOCATED IN THE FIELD WHERE POSSIBLE. THE ACTUAL LOCATION OF THESE UTILITIES SHOULD BE VERIFIED BY THE CONTRACTOR—CALL BEFORE YOU DIG 1-800-922-4455.
 2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO CONSTRUCTION AND ANY DISCREPANCIES SHALL BE REPORTED TO THE DESIGN ENGINEER FOR RESOLUTION.
 3. ALL UNSUITABLE MATERIAL DISCOVERED DURING DEMOLITION SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN A SUITABLE MANNER. THE WORK SHALL INCLUDE TREES, BRUSH, STUMPS, ORGANIC MATERIALS, ETC.
 4. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN A 4' HIGH ORANGE CONSTRUCTION FENCE ALONG THE DEMOLITION LIMIT LINE. ANY OPENINGS IN THE FENCE SHALL BE CLOSED AT NIGHT, WEEKENDS OR ANY TIME DEMOLITION IS NOT TAKING PLACE.

LEGEND

---	PROPERTY LINE
---	SANITARY SEWER
---	WATER LINE
---	ELECTRICAL LINE
---	GAS LINE
---	STORM DRAINAGE
---	PROPOSED SPOT GRADE
---	EXISTING CONTOUR
---	EXISTING SPOT GRADE
---	EXISTING CURB
---	EXISTING TELEPHONE LINE
---	PARKING METER
---	WATER GATE
---	FIRE STANDPIPE
---	CONTRACT LIMIT LINE "A"
---	CONTRACT LIMIT LINE "B"
---	ITEM TO BE REMOVED
---	UTILITY OR CURBING TO BE REMOVED

THE CONTRACTOR SHALL PROVIDE FOR THE FOLLOWING DEMOLITION WORK WITHIN CONTRACT LIMIT LINE "A".

- DEMOLITION AND REMOVAL OF BUILDING.
- DEMOLITION AND REMOVAL OF SITE IMPROVEMENTS INCLUDING BUT NOT LIMITED TO BIT. PAVEMENT, SIDEWALKS, CURBING AND SIGNS.
- DISCONNECTING, CAPPING OR SEALING, AND ABANDONING SITE UTILITIES IN PLACE, INCLUDING BUT NOT LIMITED TO WATER, SANITARY, ELECTRIC, TELEPHONE, CABLE T.V., GAS AND UNDERGROUND FUEL TANKS.
- BACKFILLING ALL CAVITIES WITH CLEAN FILL, FREE OF ROCKS, DEBRIS, CLAY, LUMPS LARGER THAN 6", STUMPS, ROOTS AND OTHER ORGANIC MATERIAL. BACKFILL SHALL BE BROUGHT UP TO THE PROPOSED GRADES AS SHOWN ON SHEET L-4. ARCHITECT AND/OR CITY SHALL APPROVE BACKFILL.

SITE DEMOLITION PLAN	
HALLISEY & HERBERT CIVIL ENGINEERS & LAND SURVEYORS 2264 SILAS DEANE HIGHWAY, ROCKY HILL, CONNECTICUT	
DRAWN G.T. CHECKED K.H. DATE JAN. 01, 1995	
SCALE 1"=20'	
SHEET 2 OF 4	
JOB NO. 2300	
AUTOCAD FILE: 2300-L2.DWG	
City of Hartford DEMOLITION OF 155 MORGAN STREET HARTFORD, CT CITY PROJECT NO: F96-03	
DAYBOOK No. 011398	
L-2	