

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF HAZARDOUS MATERIAL QUANTITIES. QUANTITIES PROVIDED IN THE SPECIFICATION ARE ESTIMATES ONLY. ACTUAL FIELD CONDITIONS MAY VARY.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PERFORMING ENOUGH DEMOLITION TO ACCESS AND REMOVE ALL ASBESTOS-CONTAINING PIPE AND PIPE FITTING INSULATION. DEMOLITION WORK WILL BE PERFORMED BY THE CONTRACTOR ONLY AFTER ENGINEERING CONTROLS HAVE BEEN ESTABLISHED AND ACTIVATED.
3. THE CONTRACTOR SHALL REMOVE ALL ASBESTOS-CONTAINING MATERIALS FROM THE BUILDING AND DISPOSE OF AS ASBESTOS WASTE.
4. THE CONTRACTOR SHALL REMOVE LAMPS AND BALLASTS FROM ALL FLUORESCENT LIGHT FIXTURES PRIOR TO ASBESTOS ABATEMENT IN EACH PHASE. THESE MATERIALS SHALL BE DISPOSED OF AS MERCURY AND PCB-CONTAINING WASTES RESPECTIVELY.



**DEMOLITION OF 155 MORGAN STREET  
HARTFORD, CT**

**SHEET CONTENTS:**

**FIRST FLOOR PLAN**

**SECOND FLOOR PLAN**

DATE OF ISSUE: 1 JANUARY 1996

REVISIONS:

|                  |                |
|------------------|----------------|
| DRWN BY/CHKD BY: | AUXILIARY No.: |
|------------------|----------------|

SCALE: *1 inch = 1 foot* JOB No.: *200*

|  |             |
|--|-------------|
|  | SHEET No. : |
|--|-------------|

**A-2**

SHEET 2 OF 6

DAYBOOK NO. 011398

CITY PROJECT NO.: F040-03