



Clarke · Tamaccio
ARCHITECTS, P.C.
2074 · PARK · STREET
HARTFORD · CT · 06106 · (203) 233-6238

**DEMOLITION OF 155 MORGAN STREET
HARTFORD, CT**

BUILDING SECTION 'A-A'

REVISIONS:

7/26/61	7/26/61
---------	---------

SHEET 4 OF 6

ATTY PROJECT NO.: P410-077



GENERAL ASBESTOS ABATEMENT NOTES

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF HAZARDOUS MATERIAL QUANTITIES. QUANTITIES PROVIDED IN THE SPECIFICATION ARE ESTIMATES ONLY. ACTUAL FIELD CONDITIONS MAY VARY.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PERFORMING ENOUGH DEMOLITION TO ACCESS AND REMOVE ALL ASBESTOS-CONTAINING PIPE AND PIPE FITTING INSULATION. DEMOLITION WORK WILL BE PERFORMED BY THE CONTRACTOR ONLY AFTER ENGINEERING CONTROLS HAVE BEEN ESTABLISHED AND ACTIVATED.
3. THE CONTRACTOR SHALL REMOVE ALL ASBESTOS-CONTAINING MATERIALS FROM THE BUILDING AND DISPOSE OF AS ASBESTOS WASTE.
4. THE CONTRACTOR SHALL REMOVE LAMPS AND BALLASTS FROM ALL FLUORESCENT LIGHT FIXTURES PRIOR TO ASBESTOS ABATEMENT IN EACH PHASE. THESE MATERIALS SHALL BE DISPOSED OF AS MERCURY AND PCB-CONTAINING WASTES RESPECTIVELY.