



LEGEND
A= 0.8
B= 0.6
C= 0.4
D= 0.2
E= 0.1
● River Gaging Stations

Park River at Riverside St.

	Area-Sq.mi.	%
A	1.1	1.5
B	3.4	4.6
C	13.4	18.2
D	41.5	56.0
E	14.6	19.7
TOTAL	74.0	100.0

DISTRIBUTION OF AREAS & COEFFICIENTS

North Branch at Albany Ave.

	Area-Sq.mi.	%
A	0.2	0.9
B	0.0	0.0
C	1.6	6.2
D	19.9	78.7
E	3.6	14.2
TOTAL	25.3	100.0

South Branch at Newfield Ave.

	Area-Sq.mi.	%
A	0.9	2.2
B	0.6	1.6
C	9.2	22.7
D	19.6	48.2
E	10.3	25.3
TOTAL	40.6	100.0

**MAP OF
PARK RIVER WATERSHED**

MADE FOR
HARTFORD FLOOD COMMISSION

BY THE
DEPARTMENT OF ENGINEERING
HARTFORD, CONN.
SEP. 1937 MAY 1939
1" = 1 MILE
PLAN P-193

SHOWING RUN-OFF COEFFICIENTS
G.H.F.C. Serial No. 000502